

PATENT COOPERATION TREATY

PCT

NOTIFICATION OF ELECTION

(PCT Rule 61.2)

From the INTERNATIONAL BUREAU

To:

United States Patent and Trademark
Office
(Box PCT)
Crystal Plaza 2
Washington, DC 20231
ETATS-UNIS D'AMERIQUE

in its capacity as elected Office

Date of mailing (day/month/year)

02 October 1998 (02.10.98)

International application No.

PCT/US98/00862

Applicant's or agent's file reference

LC-302/PCT

International filing date (day/month/year)

16 January 1998 (16.01.98)

Priority date (day/month/year)

17 January 1997 (17.01.97)

Applicant

WOODS, John, G. et al

1. The designated Office is hereby notified of its election made:



in the demand filed with the International Preliminary Examining Authority on:

10 August 1998 (10.08.98)



in a notice effecting later election filed with the International Bureau on:

2. The election ☒ was

was not

made before the expiration of 19 months from the priority date or, where Rule 32 applies, within the time limit under Rule 32.2(b).

The International Bureau of WIPO
34, chemin des Colombettes
1211 Geneva 20, Switzerland

Facsimile No.: (41-22) 740.14.35

Authorized officer

Lazar Joseph Panakal

Telephone No.: (41-22) 338.83.38

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

International Application No.

International Filing Date

Name of receiving Office and "PCT International Application"

Applicant's or agent's file reference

(if desired) (12 characters maximum)

LC-302/PCT

Box No. I TITLE OF INVENTION

Process for Hydroxyalkylating Carboxylic
Acid-Functionalized Materials

Box No. II APPLICANT

Name and address: (Family name, followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

LOCTITE CORPORATION
Hartford Square North
10 Columbus Boulevard
Hartford, CT 06106-5108
US

☐ This person is also inventor.

Telephone No.
(860) 520-5000

Facsimile No.
(860) 520-5073

Teleprinter No.

State (i.e. country) of nationality:
US

State (i.e. country) of residence:
US

This person is applicant for the purposes of: ☐ all designated States ☒ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

Box No. III FURTHER APPLICANTS AND/OR (FURTHER) INVENTORS

Name and address: (Family name, followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

WOODS, John G.
5 Beechwood Road
Farmington, CT 06032
US

This person is:

☐ applicant only

☒ applicant and inventor

☐ inventor only (If this check-box is marked, do not fill in below.)

State (i.e. country) of nationality:
IE

State (i.e. country) of residence:
US

This person is applicant for the purposes of: ☐ all designated States ☐ all designated States except the United States of America ☒ the United States of America only ☐ the States indicated in the Supplemental Box

☒ Further applicants and/or (further) inventors are indicated on a continuation sheet.

Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as: ☒ agent ☐ common representative

Name and address: (Family name, followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

BAUMAN, Steven C.
Loctite Corporation
Hartford Square North
10 Columbus Boulevard
Hartford, CT 06106-5018
US

Telephone No.

(860) 520-5001

Facsimile No.

(860) 543-7527

Teleprinter No.

☐ Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

Continuation of Form No. III FURTHER APPLICANTS AND/OR (FURTHER) INVENTORS	
<i>If none of the following sub-boxes is used, this sheet is not to be included in the request.</i>	
<p>Name and address: <i>(Family name, followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)</i></p> <p style="text-align: center;">MORRILL, Susanne D. 6 Brunswick Avenue West Hartford, CT 06107 US</p>	<p>This person is:</p> <p><input type="checkbox"/> applicant only</p> <p><input checked="" type="checkbox"/> applicant and inventor</p> <p><input type="checkbox"/> inventor only <i>(If this check-box is marked, do not fill in below.)</i></p>
<p>State (i.e. country) of nationality: US</p>	<p>State (i.e. country) of residence: US</p>
<p>This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input checked="" type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box</p>	
<p>Name and address: <i>(Family name, followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)</i></p> <p style="text-align: center;">JACOBINE, Anthony F. 202 Mayflower Lane Meriden, CT 06450 US</p>	<p>This person is:</p> <p><input type="checkbox"/> applicant only</p> <p><input checked="" type="checkbox"/> applicant and inventor</p> <p><input type="checkbox"/> inventor only <i>(If this check-box is marked, do not fill in below.)</i></p>
<p>State (i.e. country) of nationality: US</p>	<p>State (i.e. country) of residence: US</p>
<p>This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input checked="" type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box</p>	
<p>Name and address: <i>(Family name, followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)</i></p>	<p>This person is:</p> <p><input type="checkbox"/> applicant only</p> <p><input type="checkbox"/> applicant and inventor</p> <p><input type="checkbox"/> inventor only <i>(If this check-box is marked, do not fill in below.)</i></p>
<p>State (i.e. country) of nationality:</p>	<p>State (i.e. country) of residence:</p>
<p>This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box</p>	
<p>Name and address: <i>(Family name, followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)</i></p>	<p>This person is:</p> <p><input type="checkbox"/> applicant only</p> <p><input type="checkbox"/> applicant and inventor</p> <p><input type="checkbox"/> inventor only <i>(If this check-box is marked, do not fill in below.)</i></p>
<p>State (i.e. country) of nationality:</p>	<p>State (i.e. country) of residence:</p>
<p>This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box</p>	
<p><input type="checkbox"/> Further applicants and/or (further) inventors are indicated on a continuation sheet.</p>	

Box No. V DESIGNATION OF STATES

The following designations are hereby made under Rule 4.9(a) (mark the applicable check-boxes; at least one must be marked):

Regional Patent

- ☐ AP ARIPO Patent: GH Ghana, KE Kenya, LS Lesotho, MW Malawi, SD Sudan, SZ Swaziland, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☐ EA Eurasian Patent: AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ EP European Patent: AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☐ OA OAPI Patent: BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line)

National Patent (if other kind of protection or treatment desired, specify on dotted line):

- | | |
|---|---|
| <input type="checkbox"/> AL Albania | <input type="checkbox"/> LV Latvia |
| <input type="checkbox"/> AM Armenia | <input type="checkbox"/> MD Republic of Moldova |
| <input type="checkbox"/> AT Austria | <input type="checkbox"/> MG Madagascar |
| <input checked="" type="checkbox"/> AU Australia | <input type="checkbox"/> MK The former Yugoslav Republic of Macedonia |
| <input type="checkbox"/> AZ Azerbaijan | |
| <input type="checkbox"/> BA Bosnia and Herzegovina | <input type="checkbox"/> MN Mongolia |
| <input type="checkbox"/> BB Barbados | <input type="checkbox"/> MW Malawi |
| <input type="checkbox"/> BG Bulgaria | <input type="checkbox"/> MX Mexico |
| <input checked="" type="checkbox"/> BR Brazil | <input type="checkbox"/> NO Norway |
| <input type="checkbox"/> BY Belarus | <input type="checkbox"/> NZ New Zealand |
| <input checked="" type="checkbox"/> CA Canada | <input type="checkbox"/> PL Poland |
| <input type="checkbox"/> CH and LI Switzerland and Liechtenstein | <input type="checkbox"/> PT Portugal |
| <input type="checkbox"/> CN China | <input type="checkbox"/> RO Romania |
| <input type="checkbox"/> CU Cuba | <input type="checkbox"/> RU Russian Federation |
| <input type="checkbox"/> CZ Czech Republic | <input type="checkbox"/> SD Sudan |
| <input type="checkbox"/> DE Germany | <input type="checkbox"/> SE Sweden |
| <input type="checkbox"/> DK Denmark | <input type="checkbox"/> SG Singapore |
| <input type="checkbox"/> EE Estonia | <input type="checkbox"/> SI Slovenia |
| <input type="checkbox"/> ES Spain | <input type="checkbox"/> SK Slovakia |
| <input type="checkbox"/> FI Finland | <input type="checkbox"/> SL Sierra Leone |
| <input type="checkbox"/> GB United Kingdom | <input type="checkbox"/> TJ Tajikistan |
| <input type="checkbox"/> GE Georgia | <input type="checkbox"/> TM Turkmenistan |
| <input type="checkbox"/> GH Ghana | <input type="checkbox"/> TR Turkey |
| <input type="checkbox"/> HU Hungary | <input type="checkbox"/> TT Trinidad and Tobago |
| <input type="checkbox"/> IL Israel | <input type="checkbox"/> UA Ukraine |
| <input type="checkbox"/> IS Iceland | <input type="checkbox"/> UG Uganda |
| <input checked="" type="checkbox"/> JP Japan | <input checked="" type="checkbox"/> US United States of America |
| <input type="checkbox"/> KE Kenya | |
| <input type="checkbox"/> KG Kyrgyzstan | <input type="checkbox"/> UZ Uzbekistan |
| <input type="checkbox"/> KP Democratic People's Republic of Korea | <input type="checkbox"/> VN Viet Nam |
| | <input type="checkbox"/> YU Yugoslavia |
| <input checked="" type="checkbox"/> KR Republic of Korea | <input type="checkbox"/> ZW Zimbabwe |
| <input type="checkbox"/> KZ Kazakstan | |
| <input type="checkbox"/> LC Saint Lucia | |
| <input type="checkbox"/> LK Sri Lanka | |
| <input type="checkbox"/> LR Liberia | |
| <input type="checkbox"/> LS Lesotho | |
| <input type="checkbox"/> LT Lithuania | |
| <input type="checkbox"/> LU Luxembourg | |

Check-boxes reserved for designating States (for the purposes of a national patent) which have become party to the PCT after issuance of this sheet:

- ☐
- ☐
- ☐
- ☐
- ☐

In addition to the designations made above, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except the designation(s) of

The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation of a designation consists of the filing of a notice specifying that designation and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit.)

Box No. VI PRIORITY CLAIMFurther priority claims are indicated in the Supplemental Box ☐

The priority of the following earlier application(s) is hereby claimed:

Country (in which, or for which, the application was filed)	Filing Date (day/month/year)	Application No.	Office of filing (only for regional or international application)
item (1) U S	17.01.1997	60/035,717	US
item (2)			
item (3)			

Mark the following check-box if the certified copy of the earlier application is to be issued by the Office which for the purposes of the present international application is the receiving Office (a fee may be required):



The receiving Office is hereby requested to prepare and transmit to the International

Bureau a certified copy of the earlier application(s) identified above as item(s):

1**Box No. VII INTERNATIONAL SEARCHING AUTHORITY**

Choice of International Searching Authority (ISA) (If two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):

ISA/ US

Earlier search Fill in where a search (international, international-type or other) by the International Searching Authority has already been carried out or requested and the Authority is now requested to base the international search, to the extent possible, on the results of that earlier search. Identify such search or request either by reference to the relevant application (or the translation thereof) or by reference to the search request:

Country (or regional Office):

Date (day/month/year):

Number:

Box No. VIII CHECK LIST

This international application contains the following number of sheets:

1. request : 4 sheets
 2. description : 34 sheets
 3. claims : 5 sheets
 4. abstract : 1 sheets
 5. drawings : 0 sheets

Total : 44 sheets


This international application is accompanied by the item(s) marked below:

1. ☐ separate signed power of attorney
 2. ☐ copy of general power of attorney
 3. ☐ statement explaining lack of signature
 4. ☐ priority document(s) identified in Box No. VI as item(s);
 5. ☒ fee calculation sheet
 6. ☐ separate indications concerning deposited microorganisms
 7. ☐ nucleotide and/or amino acid sequence listing (diskette)
 8. ☒ other (specify): Transmittal

Figure No. ____ of the drawings (if any) should accompany the abstract when it is published.

Box No. IX SIGNATURE OF APPLICANT OR AGENT

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).



BAUMAN, Steven C.

For receiving Office use only

1. Date of actual receipt of the purported international application:

3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:

4. Date of timely receipt of the required corrections under PCT Article 11(2):

5. International Searching Authority specified by the applicant:

ISA/

6. ☐ Transmittal of search copy delayed until search fee is paid

2. Drawings

____ received

____ not received

Date of receipt of the record copy by the International Bureau:

For International Bureau use only

PATENT COOPERATION TREATY

PCT

INTERNATIONAL SEARCH REPORT

(PCT Article 18 and Rules 43 and 44)

Applicant's or agent's file reference LC-302/PCT	<div style="display: flex; justify-content: space-between;"> <div style="text-align: center;">FOR FURTHER ACTION</div> <div>see Notification of Transmittal of International Search Report (Form PCT/ISA/220) as well as, where applicable, item 5 below.</div> </div>
International application No. PCT/US98/00862	<div style="display: flex; justify-content: space-between;"> <div>International filing date (<i>day/month/year</i>) 16 JANUARY 1998</div> <div>(Earliest) Priority Date 17 JANUARY 1997</div> </div>
Applicant LOCTITE CORPORATION	

This international search report has been prepared by this International Searching Authority and is transmitted to the applicant according to Article 18. A copy is being transmitted to the International Bureau.

This international search report consists of a total of 3 sheets.

☒ It is also accompanied by a copy of each prior art document cited in this report.

1. ☐ Certain claims were found unsearchable (See Box I).

2. ☒ Unity of invention is lacking (See Box II).

3. ☐ The international application contains disclosure of a nucleotide and/or amino acid sequence listing and the international search was carried out on the basis of the sequence listing

☐ filed with the international application.
☐ furnished by the applicant separately from the international application,

☐ but not accompanied by a statement to the effect that it did not include matter going beyond the disclosure in the international application as filed.
☐ transcribed by this Authority.

4. With regard to the title,

☒ the text is approved as submitted by the applicant.
☐ the text has been established by this Authority to read as follows:

5. With regard to the abstract,

☒ the text is approved as submitted by the applicant.
☐ the text has been established, according to Rule 38.2(b), by this Authority as it appears in Box III. The applicant may, within one month from the date of mailing of this international search report, submit comments to this Authority.

6. The figure of the drawings to be published with the abstract is:

Figure No. _____

☐ as suggested by the applicant.
☐ because the applicant failed to suggest a figure.
☐ because this figure better characterizes the invention.

☐ None of the figures.

CHAPTER I
PCT TELEPHONE MEMORANDUM
FOR
LACK OF UNITY OF INVENTION



PCT No.: PCT/US98/00862

Examiner: BERNARD LIPMAN

Attorney spoken to: STEVEN C. BAUMAN

Date of call: 07 APRIL 1998

- ☒ Amount of payment approved: \$200.00
- ☒ Deposit account number to be charged: 12-2135
- ☒ Attorney elected to pay for ALL additional inventions
- ☐ Attorney elected to pay only for the additional inventions covered by
 - ☐ Group(s):
 - encompassing —
 - ☐ Claim(s):
- ☐ Attorney elected NOT to pay for any additional inventions, therefore, only the first claimed invention (Group I) covered by Claim(s) _ has been searched.
- ☒ Attorney was orally advised that there is no right to protest for any group not paid for.
- ☒ Attorney was orally advised that any protest must be filed no later than 15 days from the mailing of the Search Report (PCT/ISA/210).

Time Limit For Filing A Protest

Applicant is hereby given 15 days from the mailing date of this Search Report in which to file a protest of the holding of lack of unity of invention. In accordance with PCT Rule 40.2, applicant may protest the holding of lack of unity only with respect to the group(s) paid for.

Detailed Reasons For Holding Lack Of Unity Of Invention:

Detailed Reasons For Holding Lack of Unity Of Invention:
(Continued on a separate sheet)

Note: A copy of this form must be attached to the Search Report.

**ATTACHMENT TO CHAPTER I PCT TELEPHONE MEMORANDUM
FOR
LACK OF UNITY OF INVENTION**

Detailed Reasons For Holding Lack Of Unity Of Invention:

This application contains the following inventions or groups of inventions which are not so linked as to form a single inventive concept under PCT Rule 13.1. In order for all inventions to be searched, the appropriate additional search fees must be paid.

Group I, claim(s) 1-16, drawn to a process of hydroxylation.

Group II, claim(s) 17 and 18, drawn to adhesive compositions.

The inventions listed as Groups I and II do not relate to a single inventive concept under PCT Rule 13.1 because, under PCT Rule 13.2, they lack the same or corresponding special technical features for the following reasons: the adhesives of Group II do not rely on the technical features of the process of Group I, since the hydroxylated materials of the adhesives could be made by different process.

PATENT COOPERATION TREATY

PCT

REC'D 22 DEC 1998

INTERNATIONAL PRELIMINARY EXAMINATION REPORT


(PCT Article 36 and Rule 70)

Applicant's or agent's file reference LC-302/PCT	FOR FURTHER ACTION See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)	
International application No. PCT/US98/00862	International filing date (day/month/year) 16 JANUARY 1998	Priority date (day/month/year) 17 JANUARY 1997
International Patent Classification (IPC) or national classification and IPC Please See Supplemental Sheet.		
Applicant LOCTITE CORPORATION		

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.
2. This REPORT consists of a total of 5 sheets.
- ☐ This report is also accompanied by ANNEXES, i.e., sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority. (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).
- These annexes consist of a total of 0 sheets.

3. This report contains indications relating to the following items:

- I ☒ Basis of the report
- II ☐ Priority
- III ☐ Non-establishment of report with regard to novelty, inventive step or industrial applicability
- IV ☒ Lack of unity of invention
- V ☒ Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
- VI ☐ Certain documents cited
- VII ☐ Certain defects in the international application
- VIII ☐ Certain observations on the international application

Date of submission of the demand 10 AUGUST 1998	Date of completion of this report 22 NOVEMBER 1998
Name and mailing address of the IPEA/US Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231 Facsimile No. (703) 305-3230	Authorized officer  BERNARD LIPMAN Telephone No. (703) 308-0661

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/US98/00862

I. Basis of the report

1. This report has been drawn on the basis of *(Substitute sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to the report since they do not contain amendments):*

☒ the international application as originally filed.

☒ the description, pages 1-34 , as originally filed.

pages NONE , filed with the demand.

pages NONE , filed with the letter of _____.

pages _____ , filed with the letter of _____.

☒ the claims, Nos. 1-18 , as originally filed.

Nos. NONE , as amended under Article 19.

Nos. NONE , filed with the demand.

Nos. NONE , filed with the letter of _____.

Nos. _____ , filed with the letter of _____.

☒ the drawings, sheets/fig NONE , as originally filed.

sheets/fig NONE , filed with the demand.

sheets/fig NONE , filed with the letter of _____.

sheets/fig _____ , filed with the letter of _____.

2. The amendments have resulted in the cancellation of:

☒ the description, pages NONE .

☒ the claims, Nos. NONE .

☒ the drawings, sheets/fig NONE .

3. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed, as indicated in the ~~Supplemental Box~~ Additional observations below (Rule 70.2(c)).

4. Additional observations, if necessary:

NONE

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/US98/00862

IV. Lack of unity of invention

1. In response to the invitation to restrict or pay additional fees the applicant has:

- ☐ restricted the claims.
- ☒ paid additional fees.
- ☐ paid additional fees under protest.
- ☐ neither restricted nor paid additional fees.

2. ☐ This Authority found that the requirement of unity of invention is not complied with and chose, according to Rule 68.1, not to invite the applicant to restrict or pay additional fees.

3. This Authority considers that the requirement of unity of invention in accordance with Rules 13.1, 13.2 and 13.3 is

- ☐ complied with.
- ☒ not complied with for the following reasons:

This application contains the following inventions or groups of inventions which are not so linked as to form a single inventive concept under PCT Rule 13.1. In order for all inventions to be examined, the appropriate additional examination fees must be paid.

Group I, claim(s) 1-16, drawn to a process of hydroxylation.

Group II, claim(s) 17 and 18, drawn to adhesive compositions.

The inventions listed as Groups I and II do not relate to a single inventive concept under PCT Rule 13.1 because, under PCT Rule 13.2, they lack the same or corresponding special technical features for the following reasons: the adhesives of Group II do not rely on the technical features of the process of Group I, since the hydroxylated materials of the adhesives could be made by a different process.

4. Consequently, the following parts of the international application were the subject of international preliminary examination in establishing this report:

- ☒ all parts.
- ☐ the parts relating to claims Nos. .

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/US98/00862

V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement**1. STATEMENT**

Novelty (N)

Claims 1-18 YESClaims NONE NO

Inventive Step (IS)

Claims 1-18 YESClaims NONE NO

Industrial Applicability (IA)

Claims 1-18 YESClaims NONE NO**2. CITATIONS AND EXPLANATIONS**

Claims 1-18 meet the criteria set out in PCT Article 33(2)-(4), because the prior art does not teach or fairly suggest the reaction of carboxyl functionalized materials as claimed, wherein the unsaturation and/or CN functionalities are present as required by the claimed structures, with the hydroxy alkylating agents as claimed, nor the products resulting from said reaction. The materials are taught as useful in adhesive compositions.

----- NEW CITATIONS -----

NONE

INTERNATIONAL PRELIMINARY EXAMINATION REPORT

International application No.

PCT/US98/00862

Supplemental Box

(To be used when the space in any of the preceding boxes is not sufficient)

Continuation of: Boxes I - VIII

Sheet 10

CLASSIFICATION:

The International Patent Classification (IPC) and/or the National classification are as listed below:

IPC(6): C07C 67/24, 69/82; C08F 8/00, 8/14; C08G 63/42 and US Cl.: 525/123, 328.8, 329.2, 329.3, 3343, 348, 383; 528/272, 285, 296, 298, 307, 308, 309; 560/84, 85, 86, 89, 127, 193, 194, 198

PCTWORLD INTELLECTUAL PROPERTY ORGANIZATION
International Bureau

INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification ⁶ : C07C 67/24, 69/82, C08F 8/00, 8/14, C08G 63/42	A1	(11) International Publication Number: WO 98/31655 (43) International Publication Date: 23 July 1998 (23.07.98)
(21) International Application Number: PCT/US98/00862 (22) International Filing Date: 16 January 1998 (16.01.98) (30) Priority Data: 60/035,717 17 January 1997 (17.01.97) US (71) Applicant (for all designated States except US): LOCTITE CORPORATION [US/US]; Hartford Square North, 10 Columbus Boulevard, Hartford, CT 06106-5108 (US). (72) Inventors; and (75) Inventors/Applicants (for US only): WOODS, John, G. [IE/US]; 5 Beechwood Road, Farmington, CT 06032 (US). MORRILL, Susanne, D. [US/US]; 6 Brunswick Avenue, West Hartford, CT 06107 (US). JACOBINE, Anthony, F. [US/US]; 202 Mayflower Lane, Meriden, CT 06450 (US). (74) Agent: BAUMAN, Steven, C.; Loctite Corporation, Hartford Square North, 10 Columbus Boulevard, Hartford, CT 06106-5018 (US).		(81) Designated States: AU, BR, CA, JP, KR, US, European patent (AT, BE, CH, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE). Published <i>With international search report. Before the expiration of the time limit for amending the claims and to be republished in the event of the receipt of amendments.</i>
(54) Title: PROCESS FOR HYDROXYALKYLATING CARBOXYLIC ACID-FUNCTIONALIZED MATERIALS (57) Abstract <p>The present invention relates to a process for hydroxyalkylating terminal carboxylic acid groups. More specifically, this invention provides a process for preparing hydroxyl-functionalized materials, such as butadiene nitrile polymers, from carboxylic acid-functionalized materials, such as butadiene nitrile polymers, using a carbocyclic carbonate, such as ethylene carbonate, or a carbocyclic sulfite, such as ethylene sulfite.</p>		

FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Albania	ES	Spain	LS	Lesotho	SI	Slovenia
AM	Armenia	FI	Finland	LT	Lithuania	SK	Slovakia
AT	Austria	FR	France	LU	Luxembourg	SN	Senegal
AU	Australia	GA	Gabon	LV	Latvia	SZ	Swaziland
AZ	Azerbaijan	GB	United Kingdom	MC	Monaco	TD	Chad
BA	Bosnia and Herzegovina	GE	Georgia	MD	Republic of Moldova	TG	Togo
BB	Barbados	GH	Ghana	MG	Madagascar	TJ	Tajikistan
BE	Belgium	GN	Guinea	MK	The former Yugoslav	TM	Turkmenistan
BF	Burkina Faso	GR	Greece		Republic of Macedonia	TR	Turkey
BG	Bulgaria	HU	Hungary	ML	Mali	TT	Trinidad and Tobago
BJ	Benin	IE	Ireland	MN	Mongolia	UA	Ukraine
BR	Brazil	IL	Israel	MR	Mauritania	UG	Uganda
BY	Belarus	IS	Iceland	MW	Malawi	US	United States of America
CA	Canada	IT	Italy	MX	Mexico	UZ	Uzbekistan
CF	Central African Republic	JP	Japan	NE	Niger	VN	Viet Nam
CG	Congo	KE	Kenya	NL	Netherlands	YU	Yugoslavia
CH	Switzerland	KG	Kyrgyzstan	NO	Norway	ZW	Zimbabwe
CI	Côte d'Ivoire	KP	Democratic People's	NZ	New Zealand		
CM	Cameroon		Republic of Korea	PL	Poland		
CN	China	KR	Republic of Korea	PT	Portugal		
CU	Cuba	KZ	Kazakstan	RO	Romania		
CZ	Czech Republic	LC	Saint Lucia	RU	Russian Federation		
DE	Germany	LI	Liechtenstein	SD	Sudan		
DK	Denmark	LK	Sri Lanka	SE	Sweden		
EE	Estonia	LR	Liberia	SG	Singapore		

-1-

**PROCESS FOR HYDROXYALKYLATING
CARBOXYLIC ACID-FUNCTIONALIZED MATERIALS**

BACKGROUND OF THE INVENTION

Field of the Invention

The present invention relates broadly to a process for hydroxyalkylating carboxylic acid-functionalized materials. More specifically, this invention provides a process for preparing primary hydroxyl-terminated polymers from carboxylic acid-terminated polymers, such as carboxylic acid-terminated butadiene nitrile co-polymers ("CTBNs"), using a carbocyclic carbonate, such as ethylene carbonate, or a carbocyclic sulfite, such as ethylene sulfite.

Brief Description of the Prior Art

Hydroxyl-terminated butadiene nitrile co-polymers ("HTBNs") are known, and are generally useful as extenders with difunctional polymerizable materials to add toughness to adhesive compounds, caulking compounds and potting compounds. HTBNs react rapidly through their terminal hydroxyl groups with, for instance, organic diisocyanates to form solid, high molecular weight materials of low fusibility. [See e.g., U.S. Patent No. 3,551,472 (Siebert).] They are also used in particular to form block prepolymer

resins, as taught by U.S. Patent No. 4,295,909 (Baccei), the disclosure of which is hereby incorporated herein by reference.

Certain HTBNs, such as one available under the tradename "HYCAR" 1300X29, have been manufactured commercially for some time by the B.F. Goodrich Co., Akron, Ohio. To that end, B.F. Goodrich's U.S. Patent No. 4,444,692 (Okamoto) claims a process for making such HTBNs from carboxylic acid-terminated butadiene nitriles ("CTBNs") using ethylene oxide. In fact, this process is believed to have been used to manufacture commercial quantities of HTBNs. Ethylene oxide, however, is a gaseous and hazardous material which is highly toxic and thus, at least for this reason, is undesirable as a reactant. Accordingly, different processes, particularly ones which did not employ the gaseous and highly toxic ethylene oxide and which achieve the desired result, would be viewed as desirable.

Another method of preparing HTBNs from CTBNs involves the use of diols. Indeed, B.F. Goodrich's '472 patent discloses such a method, employing diols having three to six carbon atoms in an acid-catalyzed direct esterification to yield primary hydroxyl-terminated materials with a straight-chain three to six carbon atom unit between the carboxylic acid linkage and the hydroxyl terminus. However, this process has certain undesirable features, namely the use of a large excess of the diol which is particularly troublesome to remove upon completion of the reaction, and trans-esterification which results in an increase of the molecular weight of the so-formed HTBN which in turn increases the viscosity and reduces the hydroxyl number of the resultant HTBN.

Hydroxyamide-terminated equivalents to HTBN have also been prepared by amidation of CTBN with aminoalcohols. See B.F. Goodrich's U.S. Patent No. 4,489,008 (Riew). However, such process is not particularly suitable for large-scale commercial production as aminoalcohols are not only toxic, but are used in molar excess to CTBN. Since residual aminoalcohols are difficult to remove, the final

polymer is frequently treated with maleate esters and the like to ensure complete aminoalcohol removal. This results in the formation of low molecular weight reactive plasticizers, which adversely affect the toughness of urethane resins produced from the so-prepared hydroxyamide-terminated material.

Methods of introducing an alkyl hydroxyl functional group in place of an acidic hydrogen, such as from a carboxylic acid or a phenol, are known, an example of which involves the use of ethylene carbonate together with basic materials such as potassium carbonate and the like. See U.S. Patent No. 5,019,629 (Woods). However, use of potassium carbonate in the realm of the conversion desired herein fails to yield desired HTBN. Also, U.S. Patent No. 2,448,767 (Carlson) speaks to the hydroxyethylation of certain compounds including carboxylic acids generally using ethylene carbonate or ethylene sulfite, either in the absence of a catalyst or in the presence of an acidic one like sulfuric acid or organic esters thereof, or an alkali carbonate. However, use of either no catalyst or an acidic one in the realm of the conversion desired herein also fails to yield desired HTBN.

Other methods for hydroxyalkylating materials, such as polysaccharides, are known. For instance, U.S. Patent No. 4,474,951 (Pope) speaks to and claims the hydroxyalkylation of polysaccharides using an alkylene carbonate in the presence of a catalytic amount of a quaternary ammonium halide.

In addition, U.S. Patent No. 4,513,146 (Thompson) speaks to the use of carbonates to form esters of carboxylic acids. The '146 patent is silent, however, as to cyclic carbonates for such use.

U.S. Patent No. 4,310,707 (Strege), however, speaks to and claims a method of hydroxyalkylating phenols and thiophenols using cyclic organic carbonate compounds and sodium stannate as the catalyst. U.S. Patent No. 4,261,922 (Kem) also relates to hydroxyl alkylation reactions to prepare ether compounds from cyclic organic carbonate

compounds and phenols contacted in the presence of potassium iodide catalyst. And U.S. Patent No. 4,266,046 (Wu) speaks to and claims a process for preparing esters of polycarboxylic acids which includes reacting cyclic carbonates with a polycarboxylic acid in the presence of an alkylammonium halide. The polycarbocyclic acids are exemplified as hydrocarbon radicals having from two to four carboxylic acid groups, and are selected from substituted aromatic acids, cyclohexyl acids and short chain acids.

In the context of low molar mass compounds, see Yoshino, J. Chem. Soc., Perkins Trans. I, (11) 1266 (1977).

Nevertheless, it would be desirable to demonstrate yet another way in which an hydroxyl group could be introduced to a carboxylic acid group, particularly in the case of the preparation of HTBNs (such as HTBNs having a lower alkyl, e.g., a two or three carbon unit, between the carboxylic acid functionality and the hydroxyl group), which does not involve the use of the hazardous reagent, ethylene oxide, to achieve the desired result.

SUMMARY OF INVENTION

The present invention is directed to a process for hydroxyalkylating carboxylic acid group-functionalized material. More specifically, this invention provides a process for preparing an hydroxyl-functionalized material, which includes the step of reacting a carboxylic acid-functionalized material with an amount of a carbocyclic carbonate or carbocyclic sulfite in the presence of a phase transfer catalyst under conditions sufficient to form the hydroxyl-functionalized material. In a particularly desirable aspect of the invention, the functionalized material should be a nitrile rubber, such as those found in a liquid or melt phase. The amount of carbocyclic carbonate or carbocyclic sulfite should of course be sufficient to convert the carboxylic acid groups of the carboxylic acid-functionalized material into an hydroxyl-functionalized material.

By the process of the present invention, therefore, a carboxylic acid-functionalized material is converted into an hydroxyl-functionalized material having a lower alkyl linkage (such as a two or three carbon alkyl linkage) between the prior carboxylic acid group (now an ester linkage) and the newly-formed hydroxyl group.

Also, more generally, the present invention provides a method of using carbocyclic carbonates or carbocyclic sulfites, such as ethylene carbonate or propylene carbonate (such as 1,3-propylene carbonate), or ethylene sulfite or propylene sulfite (such as 1,3-propylene sulfite), respectively, in the presence of a phase transfer catalyst as a replacement reactant in synthetic schemes presently calling for the use of carbocyclic oxides, such as ethylene oxide or propylene oxide, respectively. In such use, the carbocyclic carbonates or carbocyclic sulfites are capable of introducing an alkyl hydroxyl group to a reactive group having an acidic hydrogen, such as a carboxylic acid group.

The present invention also provides a method of purifying the so-formed hydroxylated material which includes the step of contacting the reaction mixture with an appropriate amount of an amphoteric treating agent. This purifying treatment method avoids the conventional use of a solvent to accomplish that objective.

The process of the present invention treats a carboxylic acid-functionalized material, such as CTBN, with an hydroxyalkylating reagent, such as a carbocyclic carbonate or carbocyclic sulfite, in the presence of a phase transfer catalyst to provide a corresponding hydroxyl-functionalized material, such as HTBN, in a manner which is simple, safe and commercially viable. As an unexpected result, in the case of HTBN, the so-formed HTBN demonstrates certain properties unlike those of conventionally prepared HTBNs, which may be attributable to the lack of ethylene glycol in the HTBN, see infra. The lack, or substantial lack, of such impurity results in improved performance for certain applications compared to

HTBN derived from conventional processes (e.g., using ethylene oxide). For instance, urethane block co-polymers may be prepared therefrom with improved toughness.

5 In the process according to the present invention, the hydroxyalkylating reagent, as well as the phase transfer catalyst, are non-toxic and require neither special handling conditions nor equipment. The process according to this invention also does not require a solvent for reaction and in one aspect does not require a solvent for separation or
10 purification. In addition, at least the prior process which employs ethylene oxide also requires a trialkyl amine catalyst, the entire removal of which at the completion of the reaction is difficult and the presence of which (even in residual amounts) frequently results in premature
15 polymerization of block resins formed from HTBN.

The present invention will be more readily appreciated by those of skill in the art after a reading of the detailed description of the invention which follows, together with the illustrative examples presented
20 thereafter.

DETAILED DESCRIPTION OF THE INVENTION

As noted above, this invention relates to a process for reacting carboxylic acid-functionalized
25 polymeric materials, such as terminal and/or pendant carboxylic acid-functionalized materials, with an amount of carbocyclic carbonate or carbocyclic sulfite, such as ethylene carbonate or ethylene sulfite, respectively, sufficient to cause formation of hydroxyl-functionalized
30 materials by conversion of carboxylic acid groups to hydroxyl groups with a lower alkyl linkage between the ester linkage and the newly-formed hydroxyl group.

The hydroxyalkylating reagent appropriate to convert terminal carboxylic acid groups to corresponding
35 terminal hydroxyl groups may be chosen from a variety of materials. Of particular interest are carbocyclic carbonates and carbocyclic sulfites. For instance, where a primary hydroxyl is desirable as a terminal group, an

unsubstituted carboxylic material may be chosen. That is, in the event a two or a linear three carbon linkage is desired between the ester linkage and the terminal hydroxyl group, and carbocyclic carbonate is desired as the hydroxyalkylating reagent, ethylene carbonate or 1,3-propylene carbonate should be used. Where a mixture of primary and secondary hydroxyl groups is desired as the terminal groups and carbocyclic carbonates are desired as hydroxyalkylating reagent, 2-methyl-1,2-ethylene carbonate or 3-methyl-1,3-propylene carbonate should be used. If secondary hydroxyl groups alone are desired, then 1,2-dimethyl-1,2-ethylene carbonate or 1,3-dimethyl-1,3-propylene carbonate should be used. Similarly, 1,1-dimethyl-1,2-ethylene carbonate or 1,1-dimethyl-1,3-propylene carbonate should yield a mixture of primary and tertiary hydroxyl end groups; 1,1,2-trimethyl-1,2-ethylene carbonate or 1,1,2-trimethyl-1,3-propylene carbonate should yield a mixture of secondary and tertiary hydroxyl end groups; and 1,1,2,2-tetramethyl-1,2-ethylene glycol or 1,1,2,2-tetramethyl-1,3-propylene glycol should yield tertiary hydroxyl end groups.

As for carbocyclic sulfites, ethylene sulfite and propylene sulfites (such as 1,2-propylene sulfite and 1,3-propylene sulfite) should be used. Of course, combinations of carbocyclic carbonates and carbocyclic sulfites may also be used.

Generally, a stoichiometric or a slight excess amount of the carbocyclic carbonate or carbocyclic sulfite may be used for each equivalent of carboxylic acid group present on the carboxylic acid-functionalized material. Desirably, in the case of a carbocyclic carbonate, a slight excess may be used, such as about 2.2 equivalents for each equivalent of carboxylic acid-functionalized material having two carboxylic acid groups.

As noted above, the reaction desirably proceeds in the presence of a phase transfer catalyst. The catalyst may be any material capable of accelerating the rate of

hydroxyalkylation and minimizing undesirable side reactions. Ordinarily, the catalyst is a quaternary ammonium halide and may be used in an amount in the range of about 0.005 to about 0.5 equivalents, with about 0.01 to about 0.1

5 equivalents being preferred, for each equivalent of the carboxylic acid-functionalized material. Phosphonium halides (such as triphenyl phosphonium halides like triphenyl phosphonium bromide) and sulfonium halides may also be used. See e.g., the '046 patent, the disclosure of which is hereby expressly incorporated herein by reference.


10 Specific examples of suitable quaternary ammonium halides include alkaryl ammonium halides, such as benzyltrimethyl ammonium chloride and tetralkyl ammonium halides, such as tetraethyl ammonium halides or tetrabutyl ammonium halides like bromides or iodides. Other desirable materials useful as the phase transfer catalyst include crown ethers and calixarenes. Of course, combinations of these materials may also be used. A particularly desirable catalyst in connection with the process of the present invention is tetraethylammonium iodide.

15 The carboxylic acid-functionalized materials used in the process of the present invention may be selected from a wide variety of carboxylic acid-functionalized polymers having mono- or poly-carboxylic acid groups. Included among such materials are alkenoic carboxylic acid-functionalized materials, polymers of dienes, such as butadiene, co-polymers of dienes and vinyl nitriles, such as butadiene-acrylonitrile, and alkyl acrylates, which may be prepared, for example, by known processes, such as described in B.F. Goodrich's U.S. Patent No. 3,285,949 (Siebert), and the like.

20 Other suitable materials include carboxylic acid-functionalized versions of liquid and solid polymers of conjugated diene monomers or mixtures of these monomers with co-polymerizable monomers. Examples include olefins (e.g., isobutylene), aryl olefins and substituted aryl olefins (e.g., styrene, p-chlorostyrene, p-methoxystyrene, alpha methyl styrene, vinyl naphthalene, and the like);

unsaturated organic acids (e.g., acrylic and methacrylic acids); alkyl esters of acrylic and methacrylic acids (e.g., methyl acrylate, methyl methacrylate, butylacrylate, and the like); nitriles of acrylic and methacrylic acids (e.g., acrylonitrile, methacrylonitrile, and the like); vinylidene chloride; vinyl ketones (e.g., methyl vinyl ketones); vinyl ethers; vinyl carbazole; vinyl furan; vinyl pyridine; and the like. These liquid or solid polymers may be prepared by conventional methods including mass, emulsion and solution polymerization methods. See U.S. Patent No. 3,346,631 (Boyer), the disclosure of which is hereby expressly incorporated herein by reference.


A general representation of certain desirable carboxylic acid-functionalized polymers suitable for use with the subject invention include those within structure:



where R and R¹ may be the same or different and may be selected from COOH or CAA¹-X-COOH, where A and A¹ may be the same or different and may be selected from hydrogen, halogen, cyano, or linear or branched alkyl groups having from 1 to about 5 carbon atoms and X may be selected from linear or branched alkyl groups having from 2 to about 5 carbon atoms, such as methylene, ethylene, propylene and the like.

The fraction of repeat units of the contributing repeat fragment are represented, by $c+t+v+a=1$, and n represents the average degree of polymerization.

Examples of carboxylic-acid functionalization through the CAA'-X-COOH group include



10 Specific examples of carboxylic acid-functionalized polymers which may benefit from the process of the present invention include acrylic and methacrylic acid polymers and co-polymers, carboxylic acid-functionalized hydrogenated butadiene nitrile
 15 co-polymers, carboxylic acid-terminated poly(isobutylene), carboxylic acid-terminated polyesters, polyamides, polyurethanes and polymeric acids derived from maleic anhydride co-polymers, and carboxylic acid-terminated polyethylene, polybutadiene, polyisoprene,
 20 poly(butadiene-co-acrylonitrile), poly(isobutylene), poly(butadiene-co-styrene), poly(butadiene-co-acrylonitrile-co-acrylic acid), poly(ethyl acrylate), poly(ethyl acrylate-co-n-butyl acrylate), poly(n-butyl acrylate-co-acrylonitrile), poly(butyl
 25 acrylate-co-styrene), and the like. Of course, carboxylic acid-functionalized block and graft co-polymers may also be hydroxyalkylated according to the present invention.

Of particular interest is CTBN, available commercially from B.F. Goodrich under the "HYCAR" trademark,
 30 such as "HYCAR" 1300X31. CTBN generally has a number average molecular weight in the range of about 3,100 to about 4,200, with about 3,800 being desirable, an AN content in the range of 0 to about 26% by weight, with about 10% being desirable [polymer without AN in the case of CTBN, is
 35 carboxy-terminated polybutadiene (CTB)], and terminal groups R and R¹ as shown above. With respect to contributing repeat unit fragments, CTBN has $c+t+v=1-a$, where generally

$a=0.1$, and n is in the range of about 5 to about 750, with about 53 to about 74 being desirable.

Typically, the process of the present invention may be performed by contacting together the carboxylic acid-functionalized polymer, such as CTBN, a carbocyclic carbonate, such as ethylene carbonate, and a phase transfer catalyst, such as tetrabutyl ammonium iodide, for a period of time in the range of about 0.5 hours to about 2 hours, with about 1 hour being desirable, at a temperature in the range of about 125 to about 150°C. Of course, variations of these time and temperature parameters may be desirable depending on the identity and quantity of the starting materials used. Such variations are routine and within the ambit of knowledge of those persons of skill in the art.





The so-formed hydroxyl-functionalized polymer, such as HTBN, may thereafter be used, if desired, as generated directly from the reaction mixture, or coagulated with liquid media, such as methanol and/or water, physically separated, such as by decantation, and dried under vacuum. Alternatively, the so-formed hydroxyl-functionalized material may be treated with an amphoteric treating agent, as discussed infra, followed by physical separation, such as filtration.

It may be desirable to alter the reaction conditions in order to suit the particular reagents chosen. For example, while a liquid medium, such as a solvent, ordinarily is not required to perform the process of this invention, one may be desirable if, for instance, the carboxylic acid-functionalized polymer chosen is solid at the reaction temperature or if the hydroxyalkylating reagent is insoluble in the carboxylic acid-functionalized polymer at that temperature. Appropriate solvents or liquid media capable of dissolving or dispersing the carboxylic acid-functionalized polymer and the hydroxyl-functionalized polymer formed therefrom include acetone, methyl ethyl ketone, cyclohexanone, tetrahydrofuran, dioxane, toluene, xylene(s) and combinations thereof. Ordinarily, however, the hydroxyalkylating reagent, such as carbocyclic

carbonate, may be used in an excess amount to ensure fluidity and accomplish satisfactory heat transfer. Those persons of skill in the art should of course make appropriate choices for the liquid media, when used, to achieve the desired results.

The hydroxyl-functionalized polymers produced by the process of the present invention include, of course, hydroxyalkylated versions of any of the wide variety of carboxylic acid-functionalized polymers indicated above. For instance, hydroxyalkylated versions of the carboxylic acid-functionalized polymer include those where R and R¹ may be selected from COO-X¹-OH or CAA¹-X-COO-X¹-OH, where A, A¹ and X are as defined above and X¹ is as defined by X.

Examples of hydroxyalkylated versions of carboxylic acid-functionalized polymers through the COO-X¹-OH or the CAA¹-X-COO-X¹-OH group therefore include



Specific examples of hydroxyl-functionalized polymers which may be prepared in accordance with the process of the present invention include hydroxyl-terminated polyethylene, polybutadiene, polyisoprene, poly(butadiene-co-acrylonitrile), poly(butadiene-co-styrene), poly(butadiene-co-acrylonitrile-co-acrylic acid), poly(ethyl acrylate), poly(ethyl acrylate-co-n-butyl acrylate),

poly(n-butyl acrylate-co-acrylonitrile), poly(butyl acrylate-co-styrene), and the like.

Specific examples of hydroxyl-functionalized copolymers of butadiene containing in excess of about 50% by weight of butadiene with the remainder being at least one co-polymerizable olefinically unsaturated monomer, such as acrylonitrile, alkyl acrylates and methacrylates, acrylic and methacrylic acid, and other materials known to free-radically co-polymerize with butadiene, such as styrene(s) and derivatives thereof, and other related polymerizable materials, such as are disclosed, for instance, in the '909 patent.

After the hydroxyl-functionalized polymers are formed, they are separated from the reaction mixture by precipitation in a suitable non-solvent, such as methanol. This provides purified polymer free of a phase transfer catalyst, ethylene carbonate and ethylene glycol (if ethylene carbonate is used as the carbocyclic carbonate), after removal of solvent. The so-formed polymer may also be purified through contact with an amphoteric treating agent, which removes all or substantially all of the catalyst. Such amphoteric treating agents and general uses therefor are discussed in detail in U.S. Patent Nos. 5,371,181 (Glaser) and 5,399,624 (Glaser).

The amphoteric treating agents so noted may be chosen from silicated magnesium oxide, magnesium oxide, magnesium hydroxide, calcium hydroxide, barium oxide and barium hydroxide. Of course, combinations thereof may also be employed, if desired. The average particle size of the amphoteric treating agent should be in the range of about 2 to about 200 microns. A particularly desirable amphoteric treating agent is "MAGNESOL" Polysorb 30/40 hydrated silicated magnesium oxide (commercially available from The Dallas Group of America Inc., Liberty Corner, New Jersey), which has a particle size in the range of from about 2 to about 200 microns, and an average particle size of about 50 microns.

The use of such amphoteric treating agents allows for adsorption of the catalyst from the reaction mixture and avoids the introduction of a solvent, such as methanol, which must thereafter be removed, and which is flammable.

5 After treatment, the amphoteric treating agents may be removed by physical means, such as filtration. The desirability of using the amphoteric treating agents is therefore seen not only as a purification measure, but also as a safety measure, as well as a cost-saving measure.

10 Accordingly, it is seen that a number of significant advantages may be realized by the process of the present invention, particularly when compared with known processes. For instance, a relatively innocuous coreactant is employed in the process hereof (i.e., a carbocyclic
15 carbonate, such as ethylene carbonate, or a carbocyclic sulfite, such as ethylene sulfite) as compared with the coreactant used in certain known processes (i.e., ethylene oxide). Another significant advantage is that fewer
20 impurities are formed through the use of a carbocyclic carbonate or carbocyclic sulfite reagent, and impurities originating from ethylene oxide or the amine catalyst used therewith are no longer present.

What's more, while removal of the amine catalyst in prior processes was also seen as important for promoting
25 shelf-stability of hydroxyl-terminated polymers (see e.g., the '692 patent) and stabilizing formulations containing hydroxyl-terminated polymers and acrylate diluents (such as through the observation of less gelling of the diluent component) used for making block resins (see e.g., the '909
30 patent), use of an acidic material to accomplish that objective was viewed as disadvantageous, particularly when the so-formed hydroxyl-terminated polymer was destined for use in urethane formation (such as in the preparation of block resins), as the presence of an acidic material may
35 retard urethane formation.


HTBNs so formed in accordance with the process of the present invention, as well as HTBNs generally, have many uses, though a particularly desirable one is as intermediate

monomers in the formation of block prepolymer resins. Block prepolymer resins may be viewed as one-component, polymerizable block co-polymers having rigid and flexible segments, with block resins having flexible segments derived from HTBN being particularly useful in the preparation of structural anaerobic adhesives. Products derived from such resins are ordinarily characterized by a combination of high adhesive strength, good cure through depth (surface activation) and outstanding cohesive toughness. See the '909 patent.

Thus, an additional aspect of this invention provides an adhesive and sealant composition having improved thermal and impact properties and curable though gaps of more than 40 mils.

Such a composition includes a reaction product of the hydroxyl-functionalized material formed from reacting a carboxylic acid-functionalized material with an hydroxyalkylating reagent in the presence of a phase transfer catalyst under conditions sufficient to form the hydroxyl-functionalized material; a molar excess of polyisocyanate and polyol, with the so-formed reaction product subsequently being reacted with a molar excess of a hydroxyalkyl or amino acrylate, or methacrylate; and an initiator.

Of course, the carboxylic acid-functionalized material may be one within the structure below:



where R and R¹ may be the same or different and may be selected from COOH or CAA¹-X-COOH, with A and A¹ being the same or different and being selected from hydrogen, halogen, cyano or linear or branched alkyl groups having from 1 to about 5 carbon atoms and X being selected from linear or branched alkyl groups having from 2 to about 5 carbon atoms, c+t+v+a=1, and n is an integer in the range of from about 5 to about 750.

The hydroxylating reagent may be selected from carbocyclic carbonates and carbocyclic sulfites. The polyisocyanate and the polyol may be ones which are aromatic or cycloaliphatic. The initiator may be a free-radical initiator or a photoinitiator.

A desirable adhesive and sealant composition along these lines includes one where the polyisocyanate is toluene diisocyanate or 4,4'-diisocyanate diphenyl methane and the reaction product is one from the reaction of isocyanate-terminated hydrogenated bisphenol-A with toluene diisocyanate.

Accordingly, HTBNs formed in accordance with the present invention may be used to form block prepolymer resins in accordance with the teaching of the '909 patent, such as by chemically-linking two "pre-polymers" which are subsequently "capped" with acrylate or methacrylate functionality. In this way, a "flexible" polymeric butadiene polyol segment of relatively low molecular weight is reacted with a molar excess of a "rigid" diisocyanate, such as toluene diisocyanate or methylene diisocyanate, thereby forming urethane linkages. Thus, the resin structures include a central flexible low glass transition linear polymer which is chemically linked to relatively short rigid segments, located at either end of the linear polymer through urethane groups and capped with acrylate or methacrylate groups.

The term "rigid" segment as used herein with respect to block resins includes a segment or segments containing aromatic, heterocyclic or cycloaliphatic rings, with multiple segments joined by either fusing the rings or

by a minimum number of carbon atoms (e.g., 1 to 2, if linear, or 1 to about 6, if branched) such that there is little or no flexing of the segments. The term "flexible" segment as used herein with respect to block resins includes
5 a segment of primarily linear aliphatic moieties containing internal unsaturation, with pendant functional groups, such as aromatic, heterocyclic, cycloaliphatic, and the like, as well as branching, also incorporated therein, provided no substantial interference exists with the flexible nature of
10 the linear portion.

The flexible polybutadiene or copolybutadiene having functional groups containing an active hydrogen may be reacted with a molar excess (e.g., about 0.05 to about 6) of polyisocyanate as to the concentration of the active
15 hydrogen-containing groups on the polybutadiene. In this way, a product is assured which has an isocyanate group at each end of the polybutadiene segment.


The rigid segment may be derived from the reaction of cycloaliphatic diols, such as hydrogenated bis-phenol A,
20 with two equivalents of a diisocyanate, such as toluene diisocyanate. The urethane resins are synthesized in the presence of diluent monomers, such as triethylene glycol dimethacrylate, which also have a significant influence on the cured material properties. Such block resins derived
25 from HTBN have improved thermal, chemical and impact resistance compared to other materials.

By selection of appropriate flexible and rigid segments, the material properties of the cured resins may be optimized for adhesive applications. And in order to ensure
30 rapid and complete incorporation of the flexible segment into the urethane polymer, it is desirable for the terminal hydroxyl groups of the HTBN to be primary, rather than secondary or tertiary.

Block resins may be prepared at temperatures
35 within the range of from about room temperature to about 150°C, with temperatures within the range of from about 40°C to about 120°C being particularly desirable. After addition of the flexible diol to the isocyanate-functionalized rigid


segment, the reaction should be allowed to continue to proceed for a period of time of about 0.1 to about 24 hours. In addition, if desired, the reaction may be catalyzed, and unreactive diluents may also be used to control viscosity, bearing in mind of course that the presence of unreactive diluents may affect material properties of the cured resins.

The product of this reaction may be reacted with at least a molar equivalence, based on isocyanate group content, of an hydroxy or aminoalkyl acrylate or methacrylate to form an adhesive/sealant monomer (or prepolymer) capped at both ends with acrylate or methacrylate functionality, respectively. Esters suitable for such use are of a wide variety, although particularly desirable ones may be represented by:



where X is O, S or NH, R³ may be hydrogen, halides (e.g., chlorine) and alkyl groups (e.g., methyl and ethyl); and R⁴ may be lower alkyl groups, such as linear, branched, or cyclic groups having 1 to about 8 carbon atoms, phenylene and naphthalene.

The fully-prepared monomeric block prepolymers may be represented by:



where R³ and R⁴ are as defined above; A is a polyisocyanate linkage; D is an aromatic, heterocyclic or cycloaliphatic polyol or polyamine group (e.g., a diol of a cycloaliphatic compound); Z is a polymeric or copolymeric polyol or poly radical of butadiene, the latter having a degree of

polymerization of from about 5 to about 150 and at least about 70 percent of the polybutadiene portion of the 1,4-configuration; z is an integer corresponding to the valency of Z; d is either 0 or 1; and i is 0 when d is 0, and otherwise is one less than the number of reactive hydrogen atoms of D. An asterisk indicates a urethane (-NH-COO-) or ureide (-NH-CO-NH-) linkage.

As noted above, the block prepolymer resins cure to a hard, tough resin, using any of a wide variety of known free radical initiators, which may be activated by redox, thermal or photo-initiated mechanisms.

Examples of such free radical initiators include (a) ones which perform through a redox mechanism such as benzoyl peroxide/N,N-dimethyl-p-toluidine, cumene hydroperoxide/o-benzoyl sulfimide/N,N-dimethyl-p-toluidine, and tributyl borane; (b) ones which perform under elevated temperature conditions such as benzoyl peroxide, and 2,2'-azobisisobutylnitrile; and (c) ones which perform through photo-initiators 2,2-dimethoxy-2-phenylacetophenone and benzoyl cyclohexanol.

In addition, while one aspect of the present invention as exemplified in the illustrative examples is directed to a novel process for the preparation of HTBN, as noted above, it may also be used to convert a wide range of carboxylic acid functionalized polymers and oligomers to the corresponding hydroxylated derivatives.

The following examples are provided only for illustrative purposes and are not to be construed in any way to limit the teaching hereof.

EXAMPLES

Synthesis of HTBN

Examples describing the synthesis of HTBN by the process of the present invention and the physical properties of the so-formed HTBN are presented below, with a comparison of the physical properties of the commercial HTBN, "HYCAR" 1300X29.

The CTBN used was "HYCAR" 1300X31, commercially available from B.F. Goodrich, which contains about 10% by weight of acrylonitrile, has a nominal end functionality of about 1.9 and a number average molecular weight (M_n) of about 3,800 (as determined by vapor pressure osmometry).

Example 1

To a 3-necked, 1 liter reaction flask equipped with a mechanical stirrer, thermocouple and addition funnel was introduced with stirring about 302.48 grams (about 0.08 moles) of CTBN. The CTBN was heated to a temperature of about 125°C, at which temperature about 9.23 grams (about 0.33 moles) of ethylene carbonate and about 6.98 grams (about 0.027 moles) of tetraethylammonium iodide were introduced. The temperature of the reaction mixture was then increased to about 135°C. After a period of time of about 5 minutes, the mixture was observed to darken and began to foam. Stirring and heating were continued for an additional period of time of about 55 minutes, while maintaining the reaction temperature within the range of about 125 to about 135°C. The contents of the vessel were then cooled to a temperature of about 50°C and poured, with vigorous stirring, into a vessel containing about 1 liter of methanol, at room temperature.

On standing, the crude reaction product settled to the bottom of the vessel and the methanol was decanted. The product was then washed twice with 500 ml portions of methanol, with the methanol removed by decanting after each washing. The product was then placed in a crystallizing dish and heated to a temperature of about 80°C under a vacuum and maintained under such conditions for a period of time of about 11 hours. After such time, about 250 grams of HTBN was recovered corresponding to a yield of about 83%.

The structure of the HTBN product was confirmed by spectral analyses as follows: ^1H NMR (CDCl_3): $\delta=3.83$, m, 2H and $\delta=4.23$, m, 2H; terminal methylene group protons

-C(O)OCH₂CH₂OH; IR (KBr film): 3512 cm⁻¹ (-OH); 2250 cm⁻¹ (-CN); 1745 cm⁻¹ (carbonyl group of ester).

In addition, the ¹H NMR spectrum of the HTBN product showed neither the starting reagents, ethylene carbonate and phase transfer catalyst, nor ethylene glycol, a potential hydrolysis by-product. Residual methanol from the purification step was also shown to have been removed. The spectral characteristics of the HTBN product obtained by this method were observed to be similar to those obtained from the "HYCAR" 1300X29 HTBN product.

Example 2

To a 3-necked, 500 ml reaction flask equipped with a mechanical stirrer, thermocouple and addition funnel was introduced with stirring about 159.22 grams (about 0.04 moles) of CTBN. In this case, the stirred CTBN was heated to a temperature of only about 80°C, at which temperature about 15.41 grams (about 0.18 moles) of ethylene carbonate was introduced. The temperature of the reaction mixture was then increased to about 140°C and thereafter about 3.68 grams (about 0.014 moles) of tetraethylammonium iodide was introduced. Almost immediately, gas bubbles were observed to form in the bulk mixture. Stirring and heating were continued for a period of time of about 45 minutes, while maintaining the reaction temperature within the range of about 140 to about 143°C. The contents of the flask were then cooled and about 500 ml of dichloromethane was introduced. The polymer solution so formed was transferred to a separator funnel and washed twice with about 500 ml portions of water. The organic layer was separated, dried over anhydrous sodium sulfate and then filtered.

The solution was then transferred to an evaporating dish and warmed to a temperature of about 45°C to remove most of the methylene chloride, and then heated to a temperature of about 60°C under vacuum for a period of time of about 8 hours to yield about 140.89 grams of HTBN corresponding to an about 89% recovery. The warm polymer

was then transferred to a distillation flask and heated on a rotary evaporator at a temperature of about 95°C for a period of time of about 3.5 hours under reduced pressure. The product obtained was found by NMR and IR analyses to be identical to the product described in Example 1.

Example 3

Example 1 supra was repeated using about equimolar amounts of CTBN and ethylene carbonate, the progress of which was monitored by NMR analysis (through the emergence of signals at $\delta=3.85$ and $\delta=4.23$) with a sampling frequency of about 0.5 hours. HTBN product was not detected until the reaction mixture had been heated for a period of time of about 1.5 hours. In contrast, when that reaction was performed with an about 2-fold molar excess of ethylene carbonate, substantially complete conversion of CTBN to HTBN was observed after a period of time of about 1 hour. This indicates that the reaction rate is significantly enhanced by employing excess ethylene carbonate.

Example 4

Example 1 supra was repeated with the temperature of the mixture being maintained in the range of about 100 to about 107°C throughout the heating period. NMR analysis indicated that no HTBN product had formed after a period of time of about 1 hour.

Example 5

Example 1 supra was again repeated with the temperature of the mixture being maintained in the range of about 155 to about 160°C throughout the heating period. ¹H NMR analysis indicated that the degree of hydroxyalkylation decreased from substantial completion to about 70% after a period of time of about 1.5 hours.

Example 6

To a 3-necked, 250 ml reaction flask, equipped with a mechanical stirrer, thermocouple temperature

controller and addition funnel was added about 111.82 grams (about 0.029 moles) of "HYCAR" CTBN 1300X31. The stirred polymer was heated to a temperature of about 100°C, at which temperature about 9.84 grams (about 0.11 moles) of ethylene carbonate and about 0.608 grams of *p*-toluenesulfonic acid were added. The temperature of the mixture was increased over the course of about 5 minutes and when the temperature reached about 120°C the mixture darkened in color and began to foam. The temperature of the reaction mixture was allowed to increase thereafter to about 132°C over the course of about 15 minutes. Stirring and heating were continued for an additional period of time of about 0.5 hours while maintaining the reaction temperature between about 132 and 137°C. ¹H NMR analysis indicated that HTBN product was not present in the crude reaction mixture after that time.

Example 7

To a 3-necked, 5-liter resin kettle equipped with a mechanical stirrer and thermocouple was added about 1570 grams (about 0.39 moles) of "HYCAR" 1300X31 CTBN. The stirred polymer was heated to a temperature of about 115°C, at which temperature about 152 grams (about 1.7 moles) of ethylene carbonate and about 36 grams (about 0.14 moles) of tetraethylammonium iodide as a phase transfer catalyst were added. The mixture was observed to darken in color and thereafter begin to foam.

The temperature of the mixture was increased to about 135°C, with continued stirring and heating for a total period of time of about one hour while maintaining the reaction temperature in the range of about 134 to about 136°C. The contents of the kettle were cooled to a temperature of about 70°C and about 47.2 grams of magnesium silicate ("MAGNESOL" Polysorb 30/40) were added, with stirring continued for a period of time of about 3 hours. After such time, about 15.8 grams of the filtration aid "CELITE" 503 were added, with stirring for another 15 minutes then filtered at a pressure of about 41 psi and a

temperature of about 66°C through a filter having a pore size of 25 μ . ¹H NMR spectrum of the filtered material showed that catalyst was absent. Ethylene carbonate was removed by wiped-film evaporation under reduced pressure to yield HTBN, having spectral characteristics similar to the product prepared in Example 1. Analyses showed the material to have an hydroxyl number of 23 and a carboxyl number of less than about 0.1.

Example 8

To a 3-necked, 5 liter resin kettle equipped with a mechanical stirrer, thermocouple and addition funnel was added with stirring about 1,604.11 grams (about 0.42 moles) of "HYCAR" CTBN 1300X31. The stirred polymer was heated to a temperature of about 110°C, at which temperature about 155.28 grams (about 1.76 moles) of ethylene carbonate and about 37.15 grams (0.14 moles) of tetraethylammonium iodide as the phase transfer catalyst were added. The temperature of the mixture was increased to about 126°C, and stirring and heating were continued for an additional period of time of about 175 minutes while maintaining the reaction temperature in the range of about 121 to about 128°C.

The contents of the reactor were cooled to about 60°C and about 49 grams of magnesium silicate ("MAGNASOL" Polysorb 30/40) was added. The mixture was stirred for a period of time of about 4 hours and centrifuged for a period of time of about 10 minutes at a rate of about 2,500 rpm to separate the silicate. ¹H NMR analysis indicated that substantially all of the phase transfer catalyst was removed as indicated by the disappearance of the characteristic methylene proton signal at $\delta=3.48$.

A small aliquot (about 2 grams) of the centrifuged material was heated to a temperature of about 80°C under vacuum for a period of time of about 7 hours to provide HTBN, substantially free of ethylene carbonate, having the spectral characteristics of the HTBN product prepared in accordance with Example 1.

Example 9

Carboxylic acid-functionalized materials other than HTBN were treated with hydroxyalkylating agents in accordance with the process of the present invention to yield corresponding hydroxyl-functionalized materials.

For instance, we treated trans-3-hexenoic acid (a low molar mass model compound for HTBN) with ethylene carbonate in the presence of a phase transfer catalyst to yield 2-hydroxyethyl-3-hexenoate. More specifically, trans-3-hexenoic acid (about 1.14 grams; about 0.001 moles, commercially available from Aldrich Chemical Co., Milwaukee, Wisconsin), ethylene carbonate (about 0.97 grams; about 0.001 moles) and phase transfer catalyst were added to a 25 ml reaction flask containing a magnetic stirrer. The mixture was stirred at elevated temperature conditions to effect the hydroxyethylation reaction of the hexenoic acid. The reaction yields were estimated from the ^1H NMR spectrum of the crude product mixture.

The results obtained for a variety of parameter variations (such as, identity and quantity of phase transfer catalyst, time and temperature of the reaction, and the like) are presented below in Table 1.

Table 1

Catalyst	Equivalents conc.	Temp. (°C)	Time (hours)	Yield (%)
none	--	150	2	0
Potassium carbonate	0.35	150	2	0
Tetrabutyl ammonium bromide	0.05	135	5	61
Tetrabutyl ammonium bromide	0.1	130	3	76
Tetrabutyl ammonium bromide	0.2	140	1	92
Tetrabutyl ammonium bromide	0.1	135	10	0
Tetraethyl ammonium iodide	0.2	140	0.33	51
Tetraethyl ammonium iodide	0.2	140	0.66	63
Tetraethyl ammonium iodide	0.2	140	1	77

Example 10Evaluation of HTBNMolecular Weight Determination

Initially, we measured the molecular weight of the HTBN formed in Examples 1 and 2 supra using size exclusion chromatography employing a high pressure liquid chromatography system [Styragel HR 5 μ column set (commercially available from Waters, Incorporated), with pore sizes 10^6 , 10^4 and 500 Å], equipped with a differential refractometer. The system was calibrated with conventional polystyrene standards. Tetrahydrofuran was used as a mobile phase at a flow rate of about 1 ml/min.

We examined refractometer measurements of the eluted fractions and determined the molecular weight to be about 10,100 for the commercial HTBN compared to about

10,400 and about 11,300 for the HTBN products derived from ethylene carbonate in Examples 1 and 2, respectively. Molecular weight distributions were found to be about 1.8 for each material. Thus, good agreement was found in this regard between the HTBN prepared by the process of the present invention and the commercial HTBN.

Hydroxyl Number

We also determined the hydroxyl number for HTBN prepared by the process of the present invention and its commercial counterpart. The hydroxyl number is a measure of the concentration of hydroxyl groups on the polymeric structure and is desirable to ensure that the stoichiometric equivalent of diisocyanate be employed in the production of the block-prepolymer intermediate. Hydroxyl numbers were determined here by standard titration techniques and are reported here as mg of KOH/g of polymer.

We found the commercial HTBN to possess an hydroxyl number of 22.7 and the HTBN prepared from ethylene carbonate in Examples 1 and 2 supra to possess an hydroxyl number of 22.2 and 21.4.

Acid Numbers

The acid number is the amount of free carboxylic acid and is used to determine residual unreacted carboxylic acid at the completion of the reaction. It is desirable for the HTBN to have a low acid number, particularly when the HTBN is to be used to prepare urethane resins, because acid functionalized polymers (e.g., CTBN) react only slowly and incompletely with isocyanates. We found the process of the present invention to provide materials essentially free of carboxylic acid functionality, which compares favorably with values obtained from commercial HTBN.

In order to determine the acid number of the HTBN, we used standard titration techniques and reported the acid values as mg of KOH/g of polymer. The HTBN prepared by the process of the present invention exhibited an acid number of less than 0.1, whereas the commercial HTBN exhibited an acid

number of about 2.6. Thus, it is seen that with respect to acid conversion, the process of the present invention provides greater than a twenty fold decrease in residual acid, which results in a cleaner urethane product and is desirable to ensure that the stoichiometric equivalent of diisocyanate be employed in the production of the block-prepolymer intermediate.

Presence of Residual Glycol

¹H NMR analysis of commercial HTBN showed the presence of ethylene glycol in an amount in the range of about 0.29 to about 0.43 by weight percent. The presence of ethylene glycol in HTBN prepared from CTBN and excess ethylene oxide is not entirely surprising as residual ethylene oxide may be converted to ethylene glycol by hydrolysis. However, the presence of ethylene glycol in the HTBN is disadvantageous for certain applications to the extent that it reduces the toughness of block resins derived from HTBN. While this attribute may be beneficial in certain applications, in other applications where enhanced stiffness or reactivity is required, it is desirable to have the choice of whether or not a less tough material is to be formed. That is, in the event that a less tough HTBN-derived block resin is desirable for certain applications, ethylene glycol could nevertheless be added to the HTBN. With the process of the present invention, no ethylene glycol is produced and thus a tougher HTBN-derived block resin is afforded.

Miscellaneous

Of course, since the process of the present invention does not call for a trialkyl amine coreactant, residual amine is ordinarily zero or at most minimal. Again, we used standard titration techniques to determine the presence of amine, which is reported as mg of KOH/g of polymer. The amine value for commercial HTBN was determined to be about 1.19, whereas the amine value for an HTBN prepared according to the present invention was determined

to be about 0.19. It is desirable to have a low amine value because amines contribute to variable reactivity and product instability during the preparation of the block-prepolymers.

5 Synthesis of Block Resins

 We prepared block resins in accordance with the teaching of the '909 patent from both HTBN prepared using the process of the present invention and commercially available HTBN, and thereafter evaluated the properties and characteristics of the resulting block resins. Those results are described below.

Example 11

 Block resins were prepared from HTBN prepared by the process of the present invention as follows.

 To a 3-necked, 500 ml reaction flask equipped with a mechanical stirrer, thermocouple and condenser/inlet port was introduced with stirring about 7 grams (about 0.029 moles) of hydrogenated bisphenol-A ("HBPA"), about 48.06 grams (about 0.168 moles) of triethyleneglycol dimethacrylate, about 0.27 grams (about 0.72 mmoles) of dibutyltin dilaurate, 0.04 grams (about 0.37 mmoles) of benzoquinone and about 0.96 grams (about 0.01 moles) of methacrylic acid.

 The mixture was heated to a temperature of about 70°C under a nitrogen atmosphere for a period of about 0.5 hours, and about 10.17 grams (about 0.058 moles) of toluene diisocyanate ("TDI") (80% 2,4- and 20% 2,6 isomers) was introduced dropwise over a period of time of about 2 minutes. Thereafter, a reaction exotherm was observed, during which the temperature increased to about 83°C and the mixture was observed to clarify. Heating and stirring were continued for a further period of time of about 1 hour, after which time about 56.34 grams (about 0.015 moles) of HTBN, prepared as described above in Example 1 supra, was introduced. Heating and stirring were continued for a further period of time of about 2 hours, at which time about 2.98 grams (about 0.028 moles) of 2-hydroxyethyl

methacrylate ("HEMA") and about 0.14 grams (about 0.37 mmoles) of dibutyltin dilaurate were introduced. Heating and stirring were continued for an additional period of time of about 6 hours, after which time an IR spectrum of the reaction mixture indicated that all of the isocyanate was consumed (through the disappearance of the absorption band of the isocyanate at 2265 cm^{-1}).

The reaction mixture was cooled and spectral and chromatographic analysis confirmed the cooled product to be a methacrylate-terminated urethane block co-polymer having a flexible HTBN derived center segment and rigid urethane end segments similar to the product described in Example 1 of the '909 patent, having the following structure:

HEMA--TDI--HBPA--TDI--HTBN--TDI--HBPA--TDI--HEMA

where each urethane group is indicated by the dashed line (--). This block resin is referred to hereinafter as Resin A. Size exclusion chromatography as described supra showed Resin A to have a number average molecular weight of about 19,500

Example 12

For comparative purposes, block resins were prepared from commercially available "HYCAR" 1300X29 HTBN. Since the "HYCAR" HTBN polymer contains a significant concentration of ethylene glycol, block resins prepared with that HTBN can be expected to contain, in addition to the resin above, a short rigid block derived from an ethylene glycol ("EG") center segment, having the following structure:

HEMA--TDI--HBPA--TDI--EG--TDI--HBPA--TDI--HEMA

The difference in structure representation is seen to be due to the similarity in reactivity of isocyanate with either Resin A and the block resin whose structure is depicted above (referred to hereinafter as Resin B).

With respect to the production of block resins through an isocyanate/polyol addition, while the presence of ethylene glycol may be advantageous for certain applications it is disadvantageous for the purpose of preparing toughened block resins. In this regard, ethylene glycol has substantially equivalent reactivity to the HTBN resin and results in the formation of a short, and hence rigid, urethane oligomer which in turn results in adhesive products with reduced toughness. Further, if the concentration of the ethylene glycol varies, then adhesive products with variable rheological and mechanical properties will be produced. Such variations is often viewed as unacceptable.

Example 13

Evaluation of Properties of Block Resins Molecular Weight Determination

We measured the molecular weight of the block resins as so prepared in this example using size exclusion chromatography and the protocol set forth above with respect to the HTBN materials. The number average molecular weight of Resin A was determined to be about 19,500. In contrast, the number average molecular weight of Resin B was determined to be about 18,000.

As the molecular weight of the EG prepolymer is significantly lower than that of the HTBN material, it is to be expected that the molecular weight of a blend of the EG and HTBN products will be lower than that of the HTBN formed in accordance with this invention, such as the HTBN used to prepare Resin A.

Thus, block resins prepared from the HTBN formed in accordance with the process of this invention (i.e., Resin A) demonstrated a higher number average molecular weight due, in part, to lower levels of short blocks derived from ethylene glycol, which are present in Resin B. This difference may provide further opportunities for block resins prepared from HTBN formed in accordance with this invention, such as where improved toughness and elongation

are desirable properties to extend the range of applications for adhesives, protective coatings and sealant compositions.

Example 14

5 Curing of Block Resins

We cured the block resins prepared as described in Examples 11 and 12 supra by dissolving therein about 1% by weight of the UV/visible photoinitiator "IRGACURE" 1700 [the combination of about 25% bis-(2,6-dimethoxybenzoyl)-
10 2,4-,4-trimethylpentyl phosphine oxide and about 75% 2-hydroxy-2-methyl-1-phenyl-propan-1-one, commercially available from Ciba-Geigy Corporation, Tarrytown, New York].

Each of the photoinitiator-containing block resins was applied between glass/polyester plates and cured by
15 exposure to ultraviolet light, emitted from a Fusion Systems conveyer assembly equipped with a "D" bulb and reflectors, at a fluence of 1 J/cm²/side. The resins cured to a film having a thickness of about 0.5 mm.

20 Example 15

Evaluation of Properties of Cured Block Resins

We evaluated the physical properties and characteristics of the resulting reaction product of the cured block resins, a summary of which is provided below.

25 The mechanical properties of the cured films were determined from (1) stress-strain measurements using an Instron universal tensile tester operating at a strain rate of about 0.2"/min., with a film size of about 101.6 X 6.35 mm² and (2) dynamic mechanical analysis ("DMA") using a
30 Rheometrics Analyzer II in oscillatory shear strain operating at a frequency of about 10 radians/sec., with a film size of about 25 X 12 mm². The results are presented below in Table 2:

35

Table 2

PHYSICAL PROPERTY	CURED RESIN	
	A	B
MODULUS (PSI)	54,260	56,780
STRESS AT BREAK (PSI)	2,561	2,527
STRAIN AT BREAK (PSI)	63	39
TOUGHNESS (in.lbs./cm ³)	1,206	790
T _g 1 (°C)	-55.5	-55.7
tanδ1	0.12	0.11
T _g 2 (°C)	93	112
tanδ2	0.24	0.20

The tabulated results show that the two cured block resins have similar stiffness and breaking strength. However, the elongation at break and toughness of cured Resin A are superior to that of cured Resin B.

More specifically, both cured resins show two distinct transitions in the DMA spectrum, a low temperature transition, designated T_g1, and a high temperature transition, designated T_g2. The two transitions are indicative of a two-phase morphology. The similarity of the DMA parameters (T_g, tan values) indicates a similar structure for the cured resins. The low temperature transition (at about -55°C) occurs at about the same temperature for both of the cured resins and is associated with the rubbery central segment derived from HTBN. The high temperature transition (at about +100°C) is associated with the stiffer urethane end segments and is lower for cured Resin A than for cured Resin B. The lower T_g2 value for cured Resin A may be attributed to the absence of ethylene glycol in the HTBN prepared by the process of the present invention (and hence the absence of the

corresponding rigid short chain urethane oligomer present in Resin B). This result correlates well with the increased toughness associated with cured Resin A.

¹H NMR analysis indicated the presence of ethylene glycol (about 0.5% by weight, about 24 mole percent) in the HTBN prepared in accordance with the '691 patent, or commercial HTBN. While minor in terms of weight inclusion, the presence of ethylene glycol represents a significant concentration in molar terms, to the large disparity in molecular weight between ethylene glycol and HTBN. If the hydroxyl number determined for the commercial HTBN polymer is adjusted by subtracting the estimated contribution due to ethylene glycol, the hydroxyl value attributable to the HTBN is reduced from 25.3 to 19.5. Thus, the hydroxyl number for HTBN prepared in accordance with this invention is at least comparable, if not slightly higher, than that of the commercial HTBN. Ethylene glycol was not detected in the HTBN prepared in accordance with this invention.

Amine analysis also indicated the presence of residual amine in the commercial HTBN product. This amine impurity is known to cause premature polymerization and formation of urethane/isocyanate by-products, particularly when (meth)acrylate capping reagents and diluents are employed with respect to the production of urethane prepolymers. Accordingly, it is desirable and advantageous to first remove or neutralize the amine catalyst, prior to the introduction of isocyanate monomers.


The HTBN prepared in accordance with this invention is also substantially free of carboxylic acid functionalized materials. Carboxylic acids are undesirable, since they are known to compete with hydroxyl groups for isocyanate and result in the formation of complex mixtures of ureas, anhydrides, amides and carbon dioxide.

The scope of the present invention may be gleaned from the claims.

What is Claimed Is:

1. A process for preparing an hydroxyl-functionalized material, said process comprising the step of:

reacting as reactants (a) a carboxylic acid-functionalized material represented by:



wherein R and R¹ may be the same or different and may be selected from COOH or CAA¹-X-COOH, A and A¹ may be the same or different and may be selected from hydrogen, halogen, cyano or linear or branched alkyl groups having from 1 to about 5 carbon atoms and X may be selected from linear or branched alkyl groups having from 2 to about 5 carbon atoms, c+t+v+a=1, and n is an integer in the range of from about 5 to about 750, with (b) an hydroxyalkylating reagent selected from the group consisting of carbocyclic carbonates and carbocyclic sulfites, in the presence of (c) a phase transfer catalyst, under conditions sufficient to form the hydroxyl-functionalized material.

2. The process according to Claim 1, wherein said carboxylic acid-functionalized material is selected from the group consisting of the following carboxylic acid-functionalized polymers: polyethylene, polybutadiene, polyisoprene, poly(butadiene-co-acrylonitrile), poly(isobutylene), poly-(butadiene-co-styrene),

poly(butadiene-co-acrylonitrile-co-acrylic acid), poly(ethyl acrylate), poly(ethyl acrylate-co-n-butyl acrylate), poly(n-butyl acrylate-co-acrylonitrile), poly(butyl acrylate-co-styrene), and combinations thereof.

3. The process according to Claim 1, wherein said hydroxyalkylating reactant is a member selected from the group consisting of carbocyclic carbonate, carbocyclic sulfites and combinations thereof.


4. The process according to Claim 3, wherein said carbocyclic carbonate is a member selected from the group consisting of ethylene carbonate, 1,3-propylene carbonate, 2-methyl-1,2-ethylene carbonate, 3-methyl-1,3-propylene carbonate, 1,2-dimethyl methylene carbonate, 2,2-dimethyl butylene carbonate and combinations thereof.

5. The process according to Claim 3, wherein said carbocyclic carbonate is ethylene carbonate.

6. The process according to Claim 3, wherein said carbocyclic sulfite is a member selected from the group consisting of ethylene sulfite, propylene sulfites and combinations thereof.

7. The process according to Claim 3, wherein said carbocyclic sulfite is ethylene sulfite.

8. The process according to Claim 1, wherein said hydroxyl-functionalized material is represented by:



wherein R and R^1 may be the same or different and may be selected from $COO-X'-OH$ or $CAA'-X-COO-X'-COOH$, wherein A and A' may be the same or different and may be selected from hydrogen, halogen, cyano or linear or branched alkyl groups having from 1 to about 5 carbon atoms, and X and X' may be the same or different and may be selected from linear or branched alkyl groups having from 2 to about 5 carbon atoms, $c+t+v+a=1$ and n is an integer in the range of from about 5 to about 750.

9. The process according to Claim 1, wherein said hydroxyl-functionalized material is selected from the group consisting of the following hydroxyl-functionalized polymers: polyethylene, polybutadiene, polyisoprene, poly(isobutylene), poly(butadiene-co-acrylonitrile), poly(butadiene-co-styrene), poly(butadiene-co-acrylonitrile-co-acrylic acid), poly(ethyl acrylate), poly(ethyl acrylate-co-n-butyl acrylate), poly(n-butyl acrylate-co-acrylonitrile), poly(butyl acrylate-co-styrene), and combinations thereof.

10. The process according to Claim 1, further comprising the step of providing an amphoteric treating agent in an amount sufficient to cause the

hydroxyl-functionalized material to separate from the reactants which remain and/or any by-products thereof.

11. The process according to Claim 10, wherein the amphoteric treating agent is a member selected from the group consisting of silicated magnesium oxide, magnesium oxide, magnesium hydroxide, calcium hydroxide, barium oxide, barium hydroxide and combinations thereof.

12. The process according to Claim 1, wherein the phase transfer catalyst is a member selected from the group consisting of quaternary ammonium halides, phosphonium halides, sulfonium halides, crown ethers, calixarenes and combinations thereof.

13. The process according to Claim 1, wherein the phase transfer catalyst is a member selected from the group consisting of tetrabutyl ammonium iodide, tetraethyl ammonium iodide, benzyl trimethyl ammonium chloride and ethyl triphenylphosphonium bromide.

14. The process according to Claim 1, wherein the amount of hydroxyalkylating reagent is 3 to 10 parts by weight of the carboxylic acid-functionalized material.

15. The process according to Claim 1, wherein the carboxylic acid-functionalized material is a member selected from the group consisting of carboxylic acid-functionalized polybutadiene and carboxylic acid-functionalized poly(butadiene-co-acrylonitrile).

16. Hydroxyl-functionalized materials prepared by the process according to Claim 1.

17. An adhesive, coating or sealant composition having improved toughness and elongation properties and curable through a gap of more than 40 mils, said composition comprising (a) a reaction product of (i) the

hydroxyl-functionalized material according to Claim 1, and (ii) a molar excess of a reaction product of a molar excess of an aromatic or cycloaliphatic polyisocyanate and a compound selected from the group consisting of an aromatic or cycloaliphatic polyol, the reaction product of (i) and (ii) subsequently being reacted with a molar excess of a compound selected from the group consisting of a hydroxyalkyl acrylate, a hydroxyalkyl methacrylate, an amino alkyl acrylate, an amino alkyl methacrylate and combinations thereof; and (b) an initiator selected from the group consisting of free radical initiators and photo-initiators.

18. The composition according to Claim 17, wherein the polyisocyanate is a member selected from the group consisting of toluene diisocyanate and 4,4'-diisocyanate diphenyl methane; and the reaction product in (a) is an isocyanate-terminated hydrogenated bisphenol-A and toluene diisocyanate.

INTERNATIONAL SEARCH REPORT

International application No.

PCT/US98/00862

A. CLASSIFICATION OF SUBJECT MATTER

IPC(6) :C07C 67/24, 69/82; C08F 8/00, 8/14; C08G 63/42

US CL :Please See Extra Sheet.

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

U.S. : 525/123, 328.8, 329.2, 329.3, 3343, 348, 383; 528/272, 285, 296, 298, 307, 308, 309; 560/84, 85, 86, 89, 127, 193, 194, 198

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched


Electronic data base consulted during the international search (name of data base and, where practicable, search terms used)

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category*	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
Y	US 4,266,046 A (WU) 05 May 1981, see abstract.	1-18
A	US 4,310,707 A (STREGE) 12 January 1982.	1-18
A	US 4,513,146 A (THOMPSON) 23 April 1985.	1-18
A	US 5,019,629 A (WOODS et al) 28 May 1991.	1-18

☐ Further documents are listed in the continuation of Box C.
 ☐ See patent family annex.

* Special categories of cited documents:	*T* later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
A document defining the general state of the art which is not considered to be of particular relevance	*X* document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
E earlier document published on or after the international filing date	*Y* document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art
L document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)	*A* document member of the same patent family
O document referring to an oral disclosure, use, exhibition or other means	
P document published prior to the international filing date but later than the priority date claimed	

Date of the actual completion of the international search 23 APRIL 1998	Date of mailing of the international search report 26 MAY 1998
Name and mailing address of the ISA/US Commissioner of Patents and Trademarks Box PCT Washington, D.C. 20231 Facsimile No. (703) 305-3230	Authorized officer  BERNARD LIPMAN Telephone No. (703) 308-0661

INTERNATIONAL SEARCH REPORT

International application No.
PCT/US98/00862

A. CLASSIFICATION OF SUBJECT MATTER: US CL :

525/123, 328.8, 329.2, 329.3, 3343, 348, 383; 528/272, 285, 296, 298, 307, 308, 309; 560/84, 85, 86, 89, 127, 193, 194, 198

BOX II. OBSERVATIONS WHERE UNITY OF INVENTION WAS LACKING

This ISA found multiple inventions as follows:

This application contains the following inventions or groups of inventions which are not so linked as to form a single inventive concept under PCT Rule 13.1. In order for all inventions to be searched, the appropriate additional search fees must be paid.

Group I, claim(s) 1-16, drawn to a process of hydroxylation.

Group II, claim(s) 17 and 18, drawn to adhesive compositions.

The inventions listed as Groups I and II do not relate to a single inventive concept under PCT Rule 13.1 because, under PCT Rule 13.2, they lack the same or corresponding special technical features for the following reasons: the adhesives of Group II do not rely on the technical features of the process of Group I, since the hydroxylated materials of the adhesives could be made by different process.